

SPECIAL MEETING, 5:30 P.M.

- I. CALL TO ORDER
- II. PLEDGE OF ALLEGIANCE
- III. ROLL CALL
- IV. REVIEW AGENDA
- V. NEW BUSINESS
 - a. Consider Mays Change Order
- VI. ADJOURN

Posted 7/30/18

OPEN TO THE PUBLIC

**MAYS CONSTRUCTION
SPECIALTIES, INC.**

P.O. Box 4229
Grand Junction, CO 81502
OFFICE: (970)245-0834; FAX: (970)254-8957

CHANGE ORDER

Number **CO-06**

TO: City of Creede (Owner)
P.O. Box 457
Creede, CO 81130
Attn: Guinevere Nelson - Project Mgr.
Attn: Clyde Dooley - Town Manager

| | |
|--|---|
| PHONE City of Creede FAX (719) 658-2276 | DATE July 27, 2018 |
| JOB NAME/LOCATION Willow Creek Flume Rehabilitation Project, Phase-II Const. | |
| Willow Creek Flume , Creede CO | |
| MCSI - JOB NUMBER 211895 | JOBSITE PHONE n/a |
| EXISTING CONTRACT City of Creede and MCSI (D/B) | DATE OF EXISTING CONTRACT October 24 2017 |

NOTE: This Change Order may cause increase or decrease in the Contract Time, and if so, will be stated per each line item as to the extent.

The item(s) below are NOT included in the original contract and are either for additional scopes of work or required due to any subsurface or latent physical conditions at the site that are differing materially or that could not be determined prior to the written notice to the Owner.

1) Additional pumping and dewatering of flume due to unforeseeable amounts of water seeping into the flume. Billed at the rates below.

| <u>Equipment Item</u> | <u>Daily Rate</u> | <u>Weekly Rate*</u> | |
|---|-------------------|---------------------|--------------------------|
| Submersible -Pump 2" - 1HP Elec. w/50' cord | \$90.00 | \$405.00 | Hoses or pipes included |
| Submersible -Pump 3" - 1HP Elec. w/50' cord | \$110.00 | \$495.00 | Hoses or pipes included |
| 40KW Diesel Generator Trailer (MCSI's) | \$405.00 | \$1,822.50 | |
| 20KW Diesel Generator Trailer | \$360.00 | \$1,620.00 | |
| 6kw Generator Portable | \$118.00 | \$531.00 | |
| Labor: Set-up Pumps & Generator per Day | \$110.00 | \$660.00 | Based on 2/hours per day |
| Equip. Time: Move Gen-trailer & Pumps | \$12.00 | \$72.00 | |

All equipment used per day will be billed.

*Weekly rates based on 6-Days.

2) Sump-Holes in flume invert for dewatering pumps. Each approximately 3 to 4 sq.ft. x 1.5' to 2.5' deep as needed.

Includes demolition of grout and stones, excavation, and backfill prior to shotcrete/concrete patching.

Billed @ \$485.00/Each

Note: Upon investigation during the flume walkthrough on July 12th it was noticed that steady streams of water was flowing into the flume at multiple areas along the toe of the slopes at each side. The need for additional dewatering pumps was discussed and that reducing the water would be required to properly place shotcrete. There was and is no way to determine the source, amount or piping of the water and each section of the flume prior to bypassing the creek water and starting to dewater.


REVISED Contract Time for this Change Order: Days Increased 3 or Decreased 0. Revised substantial completion **Sept. 15th, 2018.**

Line items above include P&P Bond fees per contract agreement.

NOTE: This Change Order becomes part of and in conformance with the existing contract.

WE AGREE hereby to make the change(s) specified above at this price of :

\$ Per Unit Costs Above

| | | | |
|--|---------------------------------------|--------------------------|------------------------|
| DATE 7/27/18 | by Kyle R. Vanderberg, Vice President | PREVIOUS CONTRACT AMOUNT | \$ 1,277,189.00 |
| AUTHORIZED SIGNATURE (D/B CONTRACTOR)  | | REVISED CONTRACT AMOUNT | \$ TBD |

ACCEPTED

The above prices, scope(s) of work and specifications of this Change Order are satisfactory and are hereby accepted. All work to be performed under same terms and conditions as specified in original contract unless otherwise specified.

Approved by _____
Date of Acceptance _____
Signature _____
Print _____